Certificate / Certificat
Zertifikat / 合格証

CAM 2309039 C001

exida hereby confirms that the:

Gate Valve – Bolted Bonnet

CAMTECH Manufacturing FZCO
Jebel Ali Free Zone, Dubai - UAE

Has been assessed per the relevant requirements of:

IEC 61508 : 2010 Parts 1-2

and meets requirements providing a level of integrity to:

Systematic Capability: SC 3 (SIL 3 Capable)

Random Capability: Type A, Route 2_H Device

PFH/PFD_{avg} and Architecture Constraints must be verified for each application

Safety Function:

The Gate Valve will move to the designed safe position per the actuator design within the specified safety time.

Application Restrictions:

The unit must be properly designed into a Safety Instrumented Function per the Safety Manual requirements.

The manufacturer may use the mark:

Revision 2.0 September 25, 2026
Surveillance Audit Due
October 1, 2029

ANAB
ANSI National Accreditation Board
ACCREDITED
ISO/IEC 17065
PRODUCT CERTIFICATION BODY
#1004

exida Certification

Khaled Esmat
Evaluating Assessor

Certifying Assessor

Certificate / Certificat / Zertifikat / 合格証

CAM 2309039 C001

Systematic Capability: SC 3 (SIL 3 Capable)

Random Capability: Type A, Route 2_H Device

PFH/PFD_{avg} and Architecture Constraints must be verified for each application

Gate Valve – Bolted Bonnet

Systematic Capability:

The product has met manufacturer design process requirements of Safety Integrity Level (SIL) 3. These are intended to achieve sufficient integrity against systematic errors of design by the manufacturer.

A Safety Instrumented Function (SIF) designed with this product must not be used at a SIL level higher than stated.

Random Capability:

The SIL limit imposed by the Architectural Constraints must be met for each element. This device meets *exida* criteria for Route 2_H.

Versions:

Valve Type/Configuration	Pressure Class	Bore Sizes
Gate Valve – Bolted Bonnet	CL 150	2” – 56”
	CL 300 & CL 600	2” – 48”
	CL 900 & CL 1500	2” – 24”
	CL 2500	2” – 12”

IEC 61508 Failure Rates in FIT*

Static Application	λ_{SD}	λ_{SU}	λ_{DD}	λ_{DU}
Full Stroke, Clean Service	0	0	0	441
Tight Shut-Off, Clean Service	0	0	0	1331
Open On Trip, Clean Service	0	86	0	355

* FIT = 1 failure / 10^9 hours

SIL Verification:

The Safety Integrity Level (SIL) of an entire Safety Instrumented Function (SIF) must be verified via a calculation of PFH/PFD_{avg} considering redundant architectures, proof test interval, proof test effectiveness, any automatic diagnostics, average repair time and the specific failure rates of all products included in the SIF. Each element must be checked to assure compliance with minimum hardware fault tolerance (HFT) requirements.

The following documents are a mandatory part of certification:

Assessment Report: CAM 23/09-039 R002 V1R2 (or later)

Safety Manual: CAM-TS-0036-00-10/23 Rev 0., dated 11.11.2023 (or later)

80 N Main St
Sellersville, PA 18960